

Aviation / Construction

North End-Around Taxiway (NEAT) Extension

The Fourth Parallel Runway Program – North End-Around Taxiway (NEAT) Extension – Volume I includes the construction of 75 feet wide x 5,300 feet long new taxiway with two connector taxiways. Primary work elements include 18-inch Portland cement concrete pavement; cement-treated base course; crushed aggregate base course; asphalt shoulders; pavement markings; mass grading; 15" – 84" drainage pipes; cast-in-place and pre-cast structures; underdrains; airfield electrical including duct banks, cabling, lighting, and signage; erosion control; asphalt service roads; and fencing. The project also includes Stockpile Site – Volume II. Primary work elements include pavement, slab on grade, and foundation demolition; building demolition; utility removal; asphalt roadway; waterline installation; mass grading; erosion control; and fencing.

Details

Posting Number 2024-Q2(Apr-Jun)-AVI-12916

Anticipated Posting Date 2024-05-07

Commodity Code(s): 74500, 90569, 91223, 91240, 91310, 96863, 98814, airfi, water

Requirements

Insurance Requirements

The City requires the awarded vendor(s) to obtain and maintain the following insurance coverage types:

Last Updated: 05/13/24

Automobile-For automobile operations liability

Constructions Bonds-For bidding, payment, completion of construction projects

General Liability-For bodily injury or property damage, arising from products, premises, completed work, personal & advertising injury

Workers Compensation-For lost wages and medical expenses of injured workers

