

Charlotte Area Transit System / Construction

Canceled - South Blvd. Light Rail Facility - 3rd Floor Roofing Replacement

- WORK COVERED BY CONTRACT DOCUMENTS
 - 1. Project Identification: The project consists of roof recover at the Charlotte Area Transit System Light Rail Administration Facility, 3200 South Boulevard, Charlotte, North Carolina.
 - Project Access: Access to the facility is at 3305 Pelton Street, Charlotte, North Carolina located of the facility.
 - 3. Base Bid: Work is generally as follows:
- 1. Removal of lightning protection system and storage for reuse.
- Removal and disposal of all existing single-ply membrane and flashings; metal flashings, scupper lin
 coping caps; installation of new polyisocyanurate roof insulation, gypsum cover board and overlay, fl
 Polyvinyl-Chloride (PVC) roof membrane and flashings, wood blocking, metal flashings, coping caps
 scupper liners and all associated miscellaneous work as specified herein.
- Complete removal of existing brick along wall above roof level at Area D; and installation of new thro
 flashing and brick replacement consisting of use of salvaged brick if in good condition and providing
 (to match existing) as required.
- 4. Reinstallation of lightning protection system upon completion of the roofing work according to specifi requirements of the original UL master label installation. The existing roof systems from top to botton follows:

Components	Areas A, B, C and D
Membrane	Fully adhered Hypalon-based single-ply membrane
Cover Board	1/2 inch gypsum fiber roof board
Insulation	Two (2) layers of 2-inch extruded polystyrene (XPS)
Underlayment	5/8 inch gypsum fiber roof board
Deck	Metal deck except that parts of Area A has acoustical metal deck
Drainage	Internal roof drains with overflow scuppers
Slope	1/4 inch per foot structural slope with XPS insulation drainage crickets

Requirements

Insurance Requirements

The City requires the awarded vendor(s) to obtain and maintain the following insurance coverage types:

Last Updated: 02/09/22



General Liability-For bodily injury or property damage, arising from products, premises, completed work, personal & advertising injury

Workers Compensation-For lost wages and medical expenses of injured workers

Estimated Total Value

The total project value is anticipated to be:

\$100,000 - 249,999

Contract Term

The term of the project is anticipated to be:



Through Project Completion

For Questions, Contact:

Gregory Tate

Procurement Officer

gregory.tate@cltairport.com