

Charlotte Storm Water Services / Construction

Village Lake Dr 2210

Project started due to surface depressions along roadway. City plans to remove and replace corrugated metal pipe with 83 linear feet (LF) of 8' x 4' reinforced concrete box culvert; remove and replace two headwalls; remove and replace 311 LF of 15" reinforced concrete pipe (RCP); remove and replace 42 LF 24" RCP; remove and replace 27 LF 18" RCP; bank grading; and remove and replace 85 LF 10" ductile iron pipe of sewer.

Details

Posting Number Anticipated Posting Date Commodity Code(s): 2025-Q4(Oct-Dec)-CSWS-17370 2025-11-15 74505, 91200, 91200, 91244, 91345, 92912, 92915

Requirements

Last Updated: 02/11/25

For Questions, Contact:

Jared Raff City Contact jared.raff@charlottenc.gov